Reference

NBS Publi cations



NBSIR 78-1524

Low Velocity Performance of a Jewel Bearing Vane Anemometer

by L. P. Purtell National Bureau of Standards Fluid Engineering Division Washington, D.C. 20234

September 1978

Task Report

on
Contract No. HO166198
Evaluation of the Behavior of Mine Anemometers in the NBS Low
Velocity Calibration Facility

repared for

Inited States Department of the Interior Jureau of Mines



- - - - e

QC CO

NBSIR 78-1524

LOW VELOCITY PERFORMANCE OF A JEWEL BEARING VANE ANEMOMETER

L. P. Purtell

Fluid Engineering Division
Center for Mechanical Engineering
and Process Technology
National Engineering Laboratory
National Bureau of Standards
Washington, D. C. 20234

September 1978

Task Report

Prepared for
United States Department of the Interior
Bureau of Mines



interage in lepin Berry

U.S. DEPARTMENT OF COMMERCE, Juanita M. Kreps, Secretary

Dr. Sidney Harman, Under Secretary

Jordan J. Baruch, Assistant Secretary for Science and Technology
NATIONAL BUREAU OF STANDARDS, Ernest Ambler, Director



NB\$ 114A (9)1 7 7 73.				
U.S. DI PT. OF COMM. BIBLIOGRAPHIC DATA SHEET 1. PUBLICATION O		2. Gov't Accession No.	3. Recipient	's Accession No.
4. TITLE AND SUBTITE LOW VELOCITY PERFORMANCE OF A JE	WEL BEARING		5. Publication	on Date
VANE ANEMOMETER			6. Performin	g Organization Code
7. AUTHOR(S) L. P. Purtell			8. Performin, NBSIR 7	g Organ, Report No.
9. PERFORMING ORGANIZATION NAME AND ADD				Task/Work Unit No.
NATIONAL BUREAU OF STANDARDS DEPARTMENT OF COMMERCE WASHINGTON, D.C. 20234		11. Contract/ H016619		
12. Sponsoring Organization Name and Complete Address (Street, City, State, ZIP) Office of the Assistant Director - Mining Bureau of Mines		Covered	Report & Period 77-May 31,1977	
United States Departme Washington, D. C. 2024		cerior	14. Sponsorin	ng Agency Code
15. SUPPLEMENTARY NOTES			id verdice or	
Performance of a jewel bearing v of 60.6 to 752 feet per minute i were performed in the NBS Low Ve flow of low turbulence and utili 17. KEY WORDS (six to twelve entries; alphabetical name; separated by semicolons) Airflow; anemometer; laser veloc	ncluding star locity Airflo zes a laser v	rting and stopping which we locimeter as the velocimeter as the velocimeter as the velocimeter as the velocimeter of the veloci	ng speed. provides ne velocity	The tests a uniform standard.
vane anemometer; wind tunnel. 18. AVAILABILITY XX Unlimited		19. SECURI	TY CLASS	21. NO. OF PAGES
For Official Distribution. Do Not Release t	o NTIS	(THIS R	EPORT)	
Order From Sup. of Doc., U.S. Government P Washington, D.C. 20402, <u>SD Cat. No. C13</u>	Printing Office	20. SECURI	TY CLASS	22. Price

UNCLASSIFIED

Order From National Technical Information Service (NTIS) Springfield, Virginia 22151

- FOREWORD -

This report was prepared by the National Bureau of Standards, Fluid Engineering Division, Washington, D. C. 20234, under USBM Contract Number H0166198. The contract was initiated under the Coal Mine Health and Safety Program. It was administered under the technical direction of PM&SRC, with Dr. George H. Schnakenberg, Jr., acting as the Technical Project Officer. Mr. H. R. Eveland was the contract administrator for the Bureau of Mines.

This report is a summary of the work recently completed as part of this contract during the period April 1, 1977 to May 31, 1977. This report was submitted by the author September 1978.

LIST OF SYMBOLS

U	velocity measured by laser velocimeter
U	velocity indicated by anemometer under test
U _{if}	line segments fitted to U, U, data
Ū	group mean true velocity
Ūi	group mean indicated velocity
°i	standard deviation of \mathbf{U}_{i} data from \mathbf{U}_{if}
σ	standard deviation of \mathbf{U}_{i} data expressed as true velocity
σc	o adjusted for known variance in laser velocimeter measurements

LOW VELOCITY PERFORMANCE OF A JEWEL BEARING VANE ANEMOMETER

L. P. Purtell

1. INTRODUCTION

The National Bureau of Standards in order to meet the need for a calibration capability with adequate accuracy at low air velocities, i.e., below 500 feet per minute (fpm), undertook the development of a low-velocity calibration facility for wind speed measuring instruments which would provide a capability down to 3 meters per minute (approximately 10 fpm) with an accuracy of plus or minus one percent. It was a natural consequence therefore that when said facility became operational to undertake an evaluation of the state-of-the-art and to provide the information needed as to the reliability and performance of instrumentation for such measurement. Accordingly, a number of prototypes of various types of instruments for low velocity air measurements are undergoing test at NBS, and this report is concerned specifically with the results of one such test.

2. THE INSTRUMENT

The rotary vane anemometer tested for this report is a commercially available instrument (Sybron/Taylor Corporation, 4-Inch Anemometer, S/N H873) 1 used in the mining industry and elsewhere as a portable anemometer. It was supplied for test by the U. S. Mining Enforcement and Safety Administration (MESA) at the request of the U. S. Bureau of Mines. The housing is 4 inches in diameter and 1-3/4 inches deep (Figure 1). Thin metal vanes without camber or twist mounted on arms drive a rotor linked to a dial indicator by a gear train with jewel bearings. One revolution on the dial represents an indicated passage of 100 feet of air through the instrument. Thus an external timer (not a part of the anemometer) is required to complete a measurement of velocity (an average velocity for the duration of the measurement).

3. THE TESTS

The NBS Low Velocity Airflow Facility [1] used to test this instrument generates a low velocity air stream having a low turbulence intensity (less than 0.05%) and a large region of uniform flow (at least 75 x 75 cm). A laser velocimeter is employed as a primary velocity standard. It is nonintrusive, has a linear response with velocity, and has good spatial resolution. Adequate sensitivity is obtained without the artificial seeding of scattering particles. Thus

This particular instrument was selected as being representative of this type of anemometer and its selection does not represent an endorsement.

the difficulties and inconvenience associated with seeding and the possible effect of such seeding on the performance of the device under test are avoided.

The vane anemometer was mounted on the centerline of the tunnel test section one meter downstream of the entrance to the test section in a manner to minimize the effect of the support on the air stream around the anemometer (Figure 1). Since the anemometer itself modifies the airflow in the tunnel, the velocity should be measured at a location in the flow which has the same velocity in the presence of the anemometer as it does in the absence of the anemometer. The velocity upstream of the anemometer on the centerline was measured to find the position where deceleration of the flow due to the presence of the anemometer was no longer detectable within the scatter of the measurements. These measurements were performed at 984 fpm (Figure 2). As shown in [2] the variation of the ratio of the local velocity to the free-stream velocity with distance upstream of the anemometer is independent of free-stream velocity. A distance of 30 cm upstream of the anemometer was chosen as the position for velocity measurement by the laser velocimeter. With no anemometer in the tunnel, variation in velocity along the centerline is imperceptible over the distance traversed (30 cm).

The air speed indicated by the vane anemometer was computed from initial and final readings of the dial and of the associated time interval (around two minutes). The anemometer runs continuously in the tunnel since it cannot be accessed while the tunnel is in operation without disturbing the flow. Thus the readings of the anemometer were performed with the anemometer in operation. The laser velocimeter measurement of the air velocity was performed during the time interval for reading the vane anemometer. Five separate test runs were made, each consisting of about ten such measurements over the range 60.6 to 752 fpm. The lower velocity was limited by the starting and stopping speeds of the instrument. The data are presented in chronological order in Tables 1A to 1E.

To determine the starting speed of the instrument, the velocity in the tunnel was increased from below the starting speed at a smooth acceleration of approximately 30 fpm/min until movement of the vanes could be detected by eye. At that moment the air velocity would be fixed and the laser velocimeter measurements initiated. If the anemometer continued rotating for at least thirty seconds and did not decelerate, the measurement of velocity by the laser velocimeter was recorded as the starting speed. Ten such measurements are presented in Table 2 and have an average of 66.6 fpm and a standard deviation of 1.8 fpm.

Because of the anemometer's angular momentum, stopping speed is more difficult to determine than starting speed. Some preliminary runs indicated that a two-minute interval between reductions in air velocity of approximately 2 fpm was sufficient for the anemometer to come to rest if the stopping speed had been reached. Ten such measurements are presented in Table 3 with an average of 60.6 fpm and a standard deviation of 0.6 fpm.

4. TEST RESULTS

Since a particular air speed in the wind tunnel cannot be exactly reset from run to run, scatter in the test data is distributed along a curve, thus prohibiting computing the standard deviation of the data from a simple average. Instead, deviations from a curve fit to the data were computed and the standard deviation approximated by the r.m.s. value of these deviations within a group. The groups

U < 70 fpm 70 fpm < U < 80 fpm 80 fpm < U < 120 fpm 120 fpm < U < 180 fpm 180 fpm < U < 300 fpm 300 fpm < U < 400 fpm 400 fpm < U < 550 fpm 550 fpm < U < 650 fpm 650 fpm < U

Since a curve fit to the data would have very little curvature and since the groups of data are compact (small range of U within a group; see Figure 3), a straight line segment is used to approximate the curve within a group. The line segment passes through the point $(\overline{U},\overline{U}_i)$, the group mean true velocity and the group mean indicated velocity. The slope of the line segment is computed as the average of the slopes of two lines, both passing through $(\overline{U},\overline{U}_i)$ of the group being considered, one line passing through the $(\overline{U},\overline{U}_i)$ of the adjacent group higher in velocity, and one line passing through $(\overline{U},\overline{U}_i)$ of the adjacent group lower in velocity. For the highest group $(\overline{U} > 650 \text{ fpm})$ there is only one adjacent group, and thus the line segment for this highest group passes through $(\overline{U},\overline{U}_i)$ of that adjacent group. The line segment for the lowest group $(\overline{U} < 70 \text{ fpm})$ is similarly formed.

Designating the above line segments as Uif, the standard deviation, oi of the indicated velocity, Ui, about the fitted segments is determined by squaring the differences between the U_i data and U_{if} , i.e., $[U_i(U)]$ $U_{if}(U)$]². Since the data within the specified groups are reasonably compact, the mean of the squared differences within a group is taken as an estimate of the variance of U; about U;f within that group and specified at that group's mean true velocity, \overline{U} . To convert this to a standard deviation in terms of true velocity, designated σ , each $\sigma_i(\overline{U})$ is divided by the slope $(dU_{i,f}/dU)$ of the line segment associated with the $\sigma_{i}(U)$. Note that this ordoes not include the "scatter" in the U measurements (due to the inability to exactly reset the wind tunnel to a specified speed), but does include the uncertainty in a particular laser velocimeter measurement. This uncertainty may be estimated from repeated measurements of velocity at a particular fan setting, thus also including any unsteadiness in the velocity, and is estimated as 0.002U for this report. A standard deviation, σ_c , corrected for the laser velocimeter uncertainty may thus be computed from

$$\sigma_{c}^{2} = \sigma^{2} - (0.002U)^{2}$$

for any given U. σ and σ are presented in Figure 4 as velocity and Figure 5 as percentage of \overline{U} . Since \pm $2\sigma_c$ is extremely close to the 95 percent confidence interval for one measurement, curves of \pm $2\sigma_c$ are also included in Figure 3 as dashed lines.

The actual differences between the true and indicated velocities, U - $U_{\rm i}$, are presented in Figure 6 and as a percentage of U in Figure 7. The curves shown in each figure have been drawn for reference only.

5. DISCUSSION OF RESULTS

The instrument performed over the speed range tested with no erratic behavior. The repeatability of the starting and stopping speeds was quite good having standard deviations of 1.8 fpm (2.7%) and 0.6 fpm (1.0%), respectively. Some general comments concerning application of the instrument follow. With any measurement problem the instrument's capabilities should be matched to the required measurement.

This anemometer is intrusive, i.e., it must be placed in the flow.

This anemometer is entirely mechanical and does not require an outside source of power.

Many other factors that can affect the suitability of an instrument for a particular application, such as turbulence or unsteadiness of the air stream, rough handling (shock and vibration), dirt and other environmental factors, time, orientation to the velocity and gravity vectors, etc., have not been tested herein but should be considered.

6. SUMMARY

The performance of a 4-inch diameter low speed vane anemometer with jewel bearings has been evaluated, including starting speed and stopping speed, at air speeds up to 752 fpm.

The starting and stopping speed measurements are presented and give an average starting speed of 66.6 fpm and an average stopping speed of 60.6 fpm.

7. REFERENCES

- 1. L. P. Purtell and P. S. Klebanoff, The NBS Low-Velocity Airflow Facility, in preparation.
- 2. L. P. Purtell, Low Velocity Performance of a Bronze Bearing Vane Anemometer, NBSIR 78-1433, 1978.

Table 1A Taylor Vane Anemometer Serial No. H873

Indicated Air Speed, fpm	True Air Speed, fpm
722	752
589	619
457	494
309	322
190	221
110	145
56.8	100
26.7	76.2
7.1	60.6
27.1	76.2

T = 22.8 °C B = 751.2 mm Hg

Table 1B
Taylor Vane Anemometer
Serial No. H873

Indicated Air Speed, fpm	True Air Speed, fpm
719	746
589	623
454	498
324	360
190	222
109	142
55.8	98.0
25.1	74.6
8.4	64.8
25.7	76.0

 $T = 22.6 \, ^{\circ}C$ $B = 753.5 \, \text{mm} \, \text{Hg}$

Table 1C Taylor Vane Anemometer Serial No. H873

Indicated Air Speed, fpm	True Air Speed, fpm
720 588	750 622
456	495
323 190	363 222
110	143
54.7	96.9
23.4	74.2 63.0
23.8	74.3

 $T = 22.6 \, ^{\circ}C$ B = 753.1 mm Hg

Table 1D
Taylor Vane Anemometer
Serial No. H873

Indicated Air Speed, fpm	True Air Speed, fpm
723	752
590	622
458	499
324	361
190	221
110 54.9 22.4 23.0	142 97.1 73.6 72.4

 $T = 22.7 \, ^{\circ}C$ B = 752.9 mm Hg

Table 1E Taylor Vane Anemometer Serial No. H873

Indicated Air Speed, fpm	True Air Speed, fpm
721	742
588	624
457	496
323	360
190	220
109	141
54.5	96.4
20.0	72.6
8.5	65.5
20.8	72.5
9.8	66.1

T = 22.8 °C B = 753.0 mm Hg

Table 2 Taylor Vane Anemometer Serial No. H873


Starting Speed, fpm	
66.0	
67.2	Average starting speed,
68.4	66.6 fpm
65.4	
64.2	Standard deviation,
	1.8 fpm
66.0	
69.0	
67.2	
63.6	
66.6	

Table 3 Taylor Vane Anemometer Serial No. H873

Stopping Speed, fpm	
61.2	
60.0	Average stopping speed,
60.0	60.6 fpm
60.6	
60.0	Standard deviation, 0.6 fpm
61.2	•
60.6	
61.8	
61.2	
61.2	



FIGURE 1. The anemometer mounted in the tunnel, showing method of support.








FIGURE 3. Indicated versus true velocity with $\pm\ 2\sigma$ curves.







 σ/\overline{U} , σ_{c}/\overline{U}

(%)

17

FIGURE 5. Standard deviation, σ , and corrected standard deviation, σ_{c} , as percent of group mean velocity.





ກ ເ⊗ື 19

FIGURE 7. Percent deviation of indicated velocity from true velocity.





